

**Bid 22-058 – Transport and Install 100-foot Tower for Fort Bend County Office of
Homeland Security & Emergency Management**

Q&A #2

Question 1: What needs to be done with the existing antennas, mounts and cables that are on the existing tower?

Answer: The Contractor shall remove existing antennas, mounts, and cables and provide to Fort Bend County.

Question 2: Are you providing the cable management for the antenna and lines to be installed at the new location?

Answer: Fort Bend County is providing the cable that is to be connected to the antenna and will run to the shelter building where the hardware is located.

Question 3: For bidding purposes, are we to quote the 21.5'x21.5'x3.5' foundation and make adjustments after a geotechnical investigation is performed?

Answer: The total bid price should meet the specifications and dimensions provided. Any adjustments would require review and Fort Bend County approval once the project has commenced.

Question 4: What antenna and cable will be provided for installation at the new site? Are there any testing requirements for the antenna and cable installation?

Answer: Yagi Antenna – mounted 50 to 60 feet up on the tower, clear of any obstruction and connected to the hardware. There is no additional testing required.